

**STATEMENT OF WORK FOR INSTALLATION OF PERIMETER
ACCESS CONTROL POINT AT BLDG 15**

1. **SCOPE** SSC-SD requires the installation of government provided equipment to comprise an access control entry point at Bldg 15. The equipment to be installed is (1) Access Control Unit (ACU) Nexsentry 4100 series, and (3) card readers Westinghouse MSRK5. Also required is a TCP/IP addressable camera and control software, which is to be purchased and installed by the contractor, to work in conjunction with the government provided equipment to provide a complete standard perimeter access control point.

2. **REQUIREMENTS** The contractor must replace existing card readers and control wiring with the supplied equipment and interface with the ACU, which will integrate with the current access control system in use at SSC-SD. The contractor will purchase and install a fixed weatherproof camera at the entry pedestal for use with the intercom and card reader to facilitate access. The contractor will purchase and install a Pan/Tilt/Zoom weatherproof camera on the roof of Bldg 15 in a designated location. These cameras are to be IP addressable, and the contractor will purchase and install hardware and software to control these cameras, interfacing with a currently installed computer.